Contents

Foreword i
Preface ii
Nomenclature viii
Roman and Greek symbols viii
Acronyms and abbreviations x
Glossary xii
Supportive normative documents xxi
1. Introduction 1
1.1 Scope 1
1.2 Detection of deterioration phenomena 2
1.2.1 Corrosion 5
1.2.2 Fatigue 7
1.2.3 Freeze-thaw cycles 8
1.2.4 Alkali-silica reactions 9
1.2.5 Seismic damage 10
1.2.6 Scour 10
1.3 Performance indicators 11
1.4 Requirements & extended performance indicators 13
1.4.1 Failure probability 13
1.4.2 Reliability index 13
1.4.3 Risk 13
1.4.4 Redundancy 14
1.4.5 Risk-based robustness index 14
1.4.6 Reliability-based robustness index 14
1.4.7 Resilience 14
1.4.8 Hazard rate function 15
2. Condition survey: testing & monitoring methods 16
2.1 Introduction 16
2.2 Strategies of testing and monitoring methods 17
2.3 Classification of testing and monitoring methods and techniques 20
2.3.1 General classification 20
2.3.2 Classification according to survey goals 22
2.4 Load-independent tests: planning, execution and documentation 25
2.4.1 General requirements on testing 25
2.4.2 Planning of NDT 25

2.4.3 Reporting of NDT results 26
2.5 Load tests: planning, execution and documentation 27
2.5.1 Goals of load tests 27
2.5.2 Planning of load tests 27
2.5.3 Service loads, load arrangement, load test protocol 28
2.5.4 Static test and dynamic load test 29
2.5.5 Acceptance criteria of load tests 30
2.5.6 Load test stages (pre, during, after) 30
2.5.7 Quality control of load tests 31
2.6 Monitoring of environmental and operational loads 31
2.6.1 Environmental loads 31
2.6.2 Industrial load monitoring 32
2.6.3 Traffic loads 32
2.6.4 Other loads 34
2.7 Number and location of monitoring sensors for local and global methods 34
2.7.1 Local Methods 34
2.7.2 Global Methods 34
2.7.3 Optimisation Methods 35
2.8 Testing data 35
2.8.1 Data recording frequency/ acquisition 35
2.8.2 Statistical processing of testing data 35
2.8.3 Basic and nominal variables 36
2.9 Data quality 37
2.9.1 Measurement uncertainty 37
2.9.2 Reliability of test methods 38
3 Condition Assessment 39
3.1 Introduction 39
3.2 The assessment chain from damage/loads to indicators 42
3.2.1 Deterioration & damage indicators 42
3.2.2 Load(s) indicators 43
3.3 Visual inspection-based condition assessment 44
3.4 NDT-based condition assessment 45
3.5 SHM-based condition assessment 45
3.5.1 Static monitoring 45
3.5.2 Vibration-based monitoring 47
3.6 Treatment of environmental & operational effects 56
3.7 Thresholds for assessment 57

4. Performance prediction & modelling including advanced methods 60
4.1 Models & parameters for degradation assessment 61
4.2 Performance models 61
4.2.1 Physics-based models 62
4.2.2 Stochastic-based models 66
4.3 Updating of performance models 74
4.3.1 Single point updating 74
4.3.2 Sequential updating 75
4.3.3 Implementation 75
4.4 Performance assessment towards lifetime assessment 76
4.4.1 Performance vs. key-performance indicators 76
4.4.2 Key-Performance Indicators 78
4.4.3 Key-Performance indicators vs. lifetime assessment 81
5. Decision making processes 83
5.1 Introduction 83
5.1.1 Stakeholders of existing structures 84
5.1.2 Necessity & target of decision-making processes 85
5.1.3 Decision-making in service life management 88
5.2 Condition assessment 90
5.2.1 Overview 90
5.2.2 Design & construction 91
5.2.3 Environmental exposure & degradation 92
5.2.4 Load history & fatigue 94
5.3 Performance modelling & prediction 96
5.3.1 Overview 96
5.2.5 Past assessment, repair, strengthening & extension 96
5.3.2 Performance parameters 97
5.3.3 Typical decisions during the static recalculation of existing structures 100
6 Case studies 104
6.1 Quantification of traffic and temperature effects on the fatigue safety of a reinforced-concrete bridge deck based on monitoring data 105
6.2 Continuous SHM system of a diffusely corroded prestressed concrete operating viaduct 106
6.3 SHM for damage detection of the external prestressing system of a highway bridge 107

6.4 Continuous monitoring of Chillon viaduct under environmental & operational variability conditions 108
6.5 Localisation of settlement in a prestressed bridge 109
6.6 Temporary closing of Autio prestressed concrete bridge due to cracking, fatigue, and strain gauge drift 110
6.7 SHM of the short and long-term behavior of a long-span prestressed concrete bridge 111
6.8 Borgoforte river bridge: environmental monitoring for a decision-support system 112
6.9 Decision making due to ground deformations for the Kiruna Mine prestressed concrete bridge 113
6.10 Reliability assessment of a prestressed concrete bridge using geometrical NDT-results 114
6.11 Optimal sensor placement on a building for seismic SHM 115
6.12 SHM and data-driven seismic damage evaluation of a seven-story RC building 116
6.13 SHM of two operating tunnels subjected to a landslide 117
6.14 SHM of Cabril dam: arch dam with cracking at the crest level 118
6.15 SHM of Cahora Bassa dam: a 170 m high arch dam in Mozambique, built in the early 70s 119
6.16 Heritage Case Study: combining NDT & core sampling to assess the state of conservation of an early 20th century RC heritage building in view of adaptive re-use 120
6.17 Cultural Heritage: Vibration-based SHM of the Brivio Bridge (1917) 121
6.18 NDT-based prediction of carbonation-induced corrosion of Tokyo's National Museum of Western Art 122
6.19 Assessment of the residual strength and durability of the prestressed wharf Hermann du Pasquier of Le Havre harbour 123
6.20 Wind turbine monitoring under environmental & operational variability 124
6.21 Monitoring early cracks in the cement concrete pavement using GPR 125
6.22 Structural health monitoring of the Mezza stadium in Milano 126
Annex 127
References 129